

Distributed by:



www.Jameco.com ♦ 1-800-831-4242

The content and copyrights of the attached
material are the property of its owner.

Quality Engineering Test Report

SERIES: SKE15B 15W DC-DC SINGLE OUTPUT CONVERTER

SAMPLE:

B: SKE15B-12 +12V / 125~1250mA
D: SKE15B-24 +24V / 62.5~625mA

NO	TEST ITEM	TEST CONDITION / SPECIFICATION	RESULT	VERDICT
1	DC INPUT VOLTAGE RANGE	I/P:TESTING SPEC: 18~36VDC O/P:FULL LOAD	B:13.4~36VDC	P
2	LINE REGULATION	I/P:18~36VDC SPEC: $\pm 0.3\%$ O/P:FULL LOAD	B: -0.1% ~ +0% D: -0% ~ +0%	P
3	LOAD REGULATION	I/P:24VDC SPEC: $\pm 0.5\%$ O/P:MIN. TO FULL LOAD	B: -0.1% ~ +0.1% D: -0.1% ~ +0%	P
4	OUTPUT VOLTAGE TOLERANCE	I/P:18~36VDC SPEC: NONE O/P:MIN. TO FULL LOAD	B: -0.1% ~ +0.1% D: -0.1% ~ +0%	P
5	RIPPLE&NOISE	I/P:24VDC SPEC: B:60mV O/P:FULL LOAD D:80mV	B: 13mV D: 25mV	P
6	DC INPUT CURRENT	I/P:24VDC SPEC: 0.8A O/P:FULL LOAD	B:0.74A	P
7	O/P VOLTAGE ACCURACY	I/P:24VDC SPEC: $\pm 2\%$ O/P:MIN. LOAD	B: -0.5%(11.94V) D: -0.3%(23.93V)	P
8	EFFICIENCY	I/P:24VDC SPEC: B:82% O/P:FULL LOAD D:83%	B: 83.8% D: 84.6%	P
9	OVER LOAD PROTECTION	I/P:24VDC SPEC: 160~250% O/P:TESTING	B: 198% D: 193%	P
10	INSULATION RESISTANCE	SPEC: I/P-O/P: 500VDC/100M Ohms MIN.	B: I/P-O/P >100M Ohms	P
11	DIELECTRIC / WITHSTAND VOLTAGE	SPEC: I/P-O/P: 1000VDC/ 1 min (10mA CUT-OFF)	B: I/P-O/P:<0.002mA	P

NEXT

NO	TEST ITEM	TEST CONDITION / SPECIFICATION		RESULT	VERDICT								
12	BURN-IN TEST	I/P:24VDC TA:28℃ O/P:FULL LOAD BURN-IN DURATION : 15 hrs		B: NO BREAK D: NO BREAK	P								
13	TEMPERATURE RISE TEST T rise OF PARTS	B: I/P :24VDC O/P :FULL LOAD AFTER 15 hrs BURN-IN TA:28℃ <table><tr><td>POSITION</td><td>SAMPLE</td><td>TEMP</td><td>Trise</td></tr><tr><td>CASE</td><td>SKE15B-12</td><td>48.4℃</td><td>20.4℃</td></tr></table>			POSITION	SAMPLE	TEMP	Trise	CASE	SKE15B-12	48.4℃	20.4℃	P
POSITION	SAMPLE	TEMP	Trise										
CASE	SKE15B-12	48.4℃	20.4℃										
14	CONSTRUCTION INSPECTION (FOR QC INSPECTION REFERENCE ONLY)	1. PACKING : 軌道型塑膠包裝 2. MARKING : MODEL 3. MECHANICAL : MODULAR TYPE, PIN :1.0Øx5mm											
DATE		SAMPLE	TEST RESULT		TEST	APPROVAL							
9.5.2002		SKE15B-12 SKE15B-24	PASS		T.K.CHENG	MAX LIN							

PREVIOUS